

TOWN OF LAKE MILLS 2017 ROAD BID

The Town of Lake Mills will receive sealed bids at 1111 South Main Street, Lake Mills, WI 53551 by May 31, 2017 at 8:00 PM and will be opened at that time.

Any questions regarding this bid should be directed to Hope Oostdik at 920-648-8234. The Town of Lake Mills reserves the right to reject any or all bids or accept the bid to be most advantageous to the Town.

NEVVILLE ROAD (from CTH B North to Airport Road 6,350 LF)

1. Add 3" of base course to roadway and shoulders.

2,910 TN @ \$_____/TN = \$_____

2. Pulverize, fine grade and shape.

14,860 SY @ \$_____/SY = \$_____

3. Furnish and install an average 2 ¼" type 3LT 58-28S asphalt pavement.

1,858 TN @ \$_____/TN = \$_____

4. Clean, sweep and tack.

14,860 SY @ \$_____/SY = \$_____

5. Furnish and install an average 1 ¾" type 4LT 58-28S asphalt pavement.

1,412 TN @ \$_____/TN = \$_____

6. Furnish and install 2 FT shoulders on both sides.

762 TN @ \$_____/TN = \$_____

TOTAL: \$_____

CONSERVATION ROAD (from Mud Lake Road West to DNR Parking Area 3,693 LF)

1. Mill butt joint, clean, sweep & tack.

7,516 SY @ \$_____/SY = \$_____

2. Furnish and install an average 1 ½" type 4LT 58-28S asphalt pavement.

676 TN @ \$_____/TN = \$_____

3. Furnish and install 2 FT shoulders on both sides.

188 TN @ \$_____/TN = \$_____

TOTAL: \$_____

NOTES

- Materials and construction shall conform to the requirements of the latest edition of the Wisconsin Department of Transportation (WDOT) specifications, sections 450, 455 and 460. Additionally, materials and construction shall also conform to the requirements the current WDOT ASP 6, 460.2.1 which includes the regression of air voids from 4.0% to 3.0% with asphalt cement.
- Omitted from the requirements will be Ride quality requirements and testing (section 440), QMP mixture sampling and testing (section 460.2.8), nuclear density testing (section 460.3.3), PG binder and tack coat sampling and testing (section 455.2.2 and 455.2.3), cold weather paving (section 450.3.2.1) and safety edge (section 450.3.2.1f).
- Mix design to be submitted to the Town prior to paving for approval.
- The Town reserves the right to test the asphalt and take densities to assure compliance.
- It is the contractor's responsibility to measure and verify quantities.
- Clean, sweep & tack shall be incidental to the work.
- Traffic control shall be incidental to the work.
- Milling of butt joints shall be incidental to the work.
- All bids shall be valid for 60 days after bid opening.

Name of Bidder: _____

Address: _____

Phone: _____ **Fax:** _____

Bidder's Signature: _____

Name (Printed or Typed): _____

Date: _____

Accepted by Town of Lake Mills

Date of Acceptance: _____