

Official Notice
Advertisement For Bids

Notice is hereby given by the Town of Lake Mills, Jefferson County, Wisconsin, will receive sealed bids for Road Construction as listed in this request until 5:00P.M., local time on Friday March 1, 2019, in the office of the Town of Lake Mills, located at 1111 South Main Street Lake Mills, WI 53551. Bids will be publicly opened and read at the Town Board meeting March 12, 2019 at 8:00 P.M. Discussion and decision will be voted on by the Town Board at that time. Documents are available to be examined by contacting the Town website and making said request. All questions may be directed to Hope Oostdik @ dutchdesign@charter.net or cell # 920-675-6464.

Ditch Excavation/ Culvert Installation :

Airport Road/ West of Newville Road /South side of roadway for approx. 400 feet / installation of two culverts to field driveways.

Reconstruction of Airport Road is slated for construction season 2019. Ditch excavation is needed to remove rocks, find an old culvert, install two new 20 foot x 15 inch galvanized metal culverts with protective extensions walls to supply two field driveways. Crushed limestone gravel at a finished grade depth of 4 inches will be required to be supplied at each field drive. Driveways proposed are marked with pavement markings on site.

Excavation is needed in the existing concrete culvert lining on the North side of the road. Removal of debris, soil and plant material from Newville Road intersection, west to the driveway that provides access to the communication tower. Further excavation is needed on the South side of the roadway to remove deposited field stone and debris. Deposited field stone stretches approximately 500 feet west from the last field driveway. Stone can be removed and installed on North and South ditches as the roadway drops in elevation at the top of the hill. Markings on pavement show deposit area to control erosion.

Excavation bid price should include all charges for installation of two new galvanized culverts with end wings. Gravel for both field drives. And all equipment, erosion control measures, manpower and fine grading and seeding on completion of excavation.

All work must be completed by June 30, 2019 prior to planned pulverization and re-pavement of the roadway in the 2019 construction season.

Successful bidder will provide the Town with Proof of Insurance and assurance the completion date is within their capacity. Payment for all services will be paid in full at completion of project and approval of Town Board at its next regular meeting post excavation and completion of this project

Hope Oostdik/ TLM Chair